

How it Works

Our Standard Post Framed Buildings Include:

- 2"x6" 2' on center wall purling and 2"x4" rake bracing at all corners
- 2"x6" 2' on center roof purling set in Simpson saddle truss hangers
- 2"x8" treated base Splash Plate and 2"x6" top purling for gutter fastener
- 10' on center laminated Post and anchor pins, with 18"x8" concrete footers on Gable walls†
- 10' on center laminated post and anchor pins, with 18"x 8" concrete footers on Side walls†
- 10' on center 4/12 engineered roof truss secured in pocketed columns, 2"x10" or greater header system, required truss bracing‡
- All Lumber is #2 or better, all metal is 100% screwed
- 29 Gauge 40 year painted metal on walls, roof, and trim.
- Standard trim includes, Rat guard base trim, outside corner and rake trim, 16" ridge cap, gutter apron, and J-channel around walk doors and window if installed
- Foam closures at ridge and eave walls for insect and bird protection



Engineered Simpson Saddle Bracket



Superior Roof System



2' On Center Girted Walls

Includes Tax, Delivery, Installation and Clean up of all Building Material

Endless Building Options Available!

† Post spacing varies based on size

‡ Pitches may vary by request